2306/303
BUILDING CONSTRUCTION, CIVIL
ENGINEERING CONSTRUCTION AND
DRAWING
Oct./Nov. 2022
Time: 3 hours



### THE KENYA NATIONAL EXAMINATIONS COUNCIL

## **DIPLOMA IN QUANTITY SURVEYING**

BUILDING CONSTRUCTION, CIVIL ENGINEERING CONSTRUCTION AND DRAWING

3 hours

### INSTRUCTIONS TO CANDIDATES

You should have the following for this examination:

Answer booklet;

Drawing instruments;

Drawing paper size A3.

This paper consists of EIGHT questions in THREE sections; A, B and C.

Answer FIVE questions; TWO questions from section A, TWO questions from section B and

ONE question from section C.

Questions in section A and B are 15 marks each while questions in section C are 40 marks each.

Maximum marks for each part of a question are as indicated.

Candidates should answer the questions in English.

This paper consists of 8 printed pages.

Candidates should check the question paper to ascertain that all the pages are printed as indicated and that no questions are missing.

© 2022 The Kenya National Examinations Council

Turn over

### SECTION A: BUILDING CONSTRUCTION

Answer TWO questions from this section.

- 1. (a) Explain each of the following systems of domestic waste water disposal:
  - (i) single stack;
  - (ii) two pipe;
  - (iii) one pipe.


(6 marks)

- (b) (i) Explain the term 'suspended ceiling'.
  - (ii) State four types of suspended ceilings.

(4 marks)

(c) Figure 1 shows a concrete portal frame. Sketch and label detail A.

(5 marks)



- 2. (a) Differentiate between the terms 'thermal restivity' and 'thermal conductivity' in building. (3 marks)
  - (b) Explain three reasons for building maintenance. (6 marks)
  - (c) Sketch and label a cross-section through a lantern light of a pitched roof. (6 marks)
- 3. (a) State six types of fences. (3 marks)
  - (b) Differentiate between 'non self centering' and 'partially centering' floors. (3 marks)
  - (c) With the aid of a labelled pictorial sketch, explain the construction of a cranked slab stair. (9 marks)

2306/303 Oct/Nov. 2022

# SECTION B: CIVIL ENGINEERING CONSTRUCTION

Answer TWO questions from this section.

| 4. | (a) | Explain three methods of permanent water exclusion in foundations.         | (6 marks)            |
|----|-----|--|----------------------|
|    | (b) | Explain the difference between remote and sock grout seals in caisson con- | struction. (4 marks) |
|    | (c) | Sketch and label a section through a railway line.                         | (5 marks)            |
| 5. | (a) | Explain each of the following terms used in airports:                      |                      |
|    |     | (i) taxiway;   |                      |
|    |     | (ii) runway excursion;   |                      |
|    |     | (iii) runway incursion.  |                      |
|    |     |  | (6 marks)            |
|    | (b) | Explain three factors considered before designing a pedestrian bridge.     | (6 marks)            |
|    | (c) | (i) Define the term spillway.  |                      |
|    |     | (ii) State three types of spillways.                                       |                      |
|    |     | No.  | (3 marks)            |
| 6. | (a) | State four types of wells.   | (2 marks)            |
|    | (b) | Explain the term tunnel as used in Civil Engineering.                      | (2 marks)            |
|    | (c) | Explain:   |                      |
| )  |     | (i) the term "waste water treatment";                                      |                      |
|    |     | (ii) two reasons for waste water treatment.                                |                      |
|    |     |  | (6 marks)            |
|    | (d) | Sketch and label a section through a diaphragm wall.                       | (5 marks)            |
|    |     |  |                      |

## **SECTION C: DRAWING**

Answer ONE question from this section.

7. **Figure 2** shows the plan of a highway and a bridge.


To a scale of 1:50 draw section X-X using the data provided:

### Data

| - | Footpath gravel                | 300 mm thick                                     |
|---|--------------------------------|--|
| - | Asphalt surfacing on footpath  | 25 mm thick                                      |
| - | Asphalt premix surfacing       | 50 mm thick                                      |
| - | Sub-base maximum depth         | 1000 mm  |
| - | Base course depth              | 500 mm   |
| - | Road kerb                      | 250 x 800 mm                                     |
| - | Flush channel                  | 250 x 700 mm                                     |
| - | Column base                    | 3000 x 3000 x 1000 mm                            |
| - | Murram blinding                | 3000 x 3000 x 200 mm                             |
| - | Trapezoidal drainage channel   | 1500 mm wide at the top and 500 mm at the bottom |
| - | Height of the drainage channel | 1100 mm  |
| - | Total column height            | 12000 mm   |
| _ | Substructure column height     | 5200 mm  |
| - | Rails                          | 200 x 200 mm                                     |
| - | Deck slab thickness            | 500 mm   |

Assume any other necessary information.

(40 marks)




8. (a) Figure 3 shows the plan of a column and column base. To a scale of 1:10 draw section Y-Y using the data provided.

### Data

| - | Depth of column base       | 600 mm             |
|---|----------------------------|--------------------|
| - | Murram blinding            | 50 mm              |
| - | Column reinforcement       | T16                |
| - | Links                      | T8 - 200           |
| - | Ground beams size          | 400 x 600 x 400 mm |
| - | Column size                | 400 x 600 mm       |
| - | Substructure column height | 800 mm             |
| - | Beam reinforcement         | 6T16               |

Assume any other information not given.

(20 marks)



160

(b) Figure 4 shows the plan of a septic tank. To a scale of 1:25 draw section Z-Z using the data provided.

#### Data

| -  | Total pit depth at wall | X-2750 mm |
|----|-------------------------|-----------|
| 40 | Total pit depth at wall | Y-2150 mm |

Wall X at a gradient from buffle wall B
Wall Y and buffle wall B at the same base

level

- Total pit depth for manhole 900 mm

MDCI cover and frame 600 x 450 mm
 Sewage level from top of base slab of wall X-1700 mm

Depth of buffle wall A
 Depth of buffle wall B
 1250 mm
 1000 mm

- Buffle wall A projects 250 mm above sewage level

- Inlet and outlet pipes 100 mm  $\phi$  UPVC

- Concrete bed in septic tank 150 mm thick

- Suspended slab thickness 200 mm

- Water proofing screed on concrete bed 20 mm thick

Plaster / render
 Thickness of concrete bed in manholes
 15 mm thick
 100 mm

Assume any other necessary information.

(20 marks)




FIGURE 4

THIS IS THE LAST PRINTED PAGE.